

HALEU Fuel Manufacturing



Douglas C. Crawford

MFC Chief Scientist

Timothy Hyde

*Director, Fuel Fabrication and Nuclear
Material Management*

www.inl.gov



GAIN-EPRI-NEI-USNIC
Micro-Reactor Workshop
June 19, 2019 – Idaho Falls, ID

INL Fuel Fabrication



- **Pu and minor actinides**
 - Fuel Manufacturing Facility (FMF)
 - Casting Laboratory (Analytical Laboratory)
- **Uranium**
 - Fuels and Applied Science Building (FASB)
 - Experimental Fuels Facility (EFF)



Transuranic glovebox line in FMF

Advanced Fuels Campaign



Metallic fuel extrusion line in EFF

TerraPower




Fuel casting furnace in FASB (U capability in EFF)



140410π
U₃Si₂ pellet sintered in FASB

Fabrication development of accident tolerant fuel (U₃Si₂)



Transmutation fuel


Fabrication process development – casting of metal fuel



Fuel experiment capsule (top) and rodlets ready for irradiation testing


Advanced Nuclear Needs Near-term HALEU Fuel for Demonstration

- **Several new reactor and fuel concepts call for use of high-assay low-enriched uranium (HALEU) fuel (U-235 enrichment from 5% to 20%)**
 - Regulatory approval may be facilitated by demonstration
 - But – no commercial HALEU supply of or capability
 - DOE and INL asked to help provide HALEU fuel
- **Insufficient DOE uranium inventory available for this purpose, so ~10 MT of HALEU from FCF spent fuel treatment to be made available**
- **DOE-funded study at INL-MFC**
 - HALEU recovery using the FCF process
 - Fuel fabrication in INL facility using gloveboxes, rather than in shielded hot cells
 - Consider generically metallic fuel and pellet-type fuel engineering-scale fuel manufacturing campaigns



Facility Options

- **Targeting Haz Cat 2 authorization**
- **MFC-798 (RLWTF)**
 - Available in late 2019
 - Need to remove contaminated piping and equipment
- **FCF Mockup Shop Area**
 - Need to first relocate current mission
 - Access restricted by security requirements
- **ZPPR Reactor Cell & Workroom**
 - Available now
 - Limited ventilation capacity and floor space
- **EBR-II Dome**
 - Best used for reactor demo?
 - Need to repair Dome & Shell and install reinforced concrete floor
- **All need HVAC work and other system mods/installs**



For Quickest-possible HALEU Fuel Delivery We Propose


- **DOE fund accelerated FCF treatment rate of EBR-II spent fuel**
 - FCF transitioned from 4x10 operation to 7x12 in April
 - Improved process to reduce radioactive contaminants in product
- **Private sector partners fund**
 - Procurement of glovebox and equipment design, build, testing, and installation
 - INL engineering and quality personnel to be engaged
 - INL preparation of process design and requirements
- **Funding source TBD, INL to execute**
 - Safety design strategy, hazard analysis, safety analysis
 - Preparation of building, including relocating current mission, building mods, HVAC design and installation



*U metal
recovered during
fuel treatment*



HALEU metallic ingots



Inert-atmosphere glovebox



*Arc-melter for
alloy/compound
preparation*

HALEU Fuel Fabrication – Current Estimates

- **Facility Preparation Cost Estimate: \$39M (-10%/+30%)**
 - Facility cleanout: \$2M
 - Facility modifications and operational readiness: \$19M
 - Equipment: \$18M
- **Operations Cost Estimate: \$106M (-10%/+30%)**
 - FCF HALEU production (increment to accelerate EBR-II fuel treatment): \$35M
 - Fuel fabrication: \$71M
- **Schedule:**
 - At 7x12 FCF operation
 - 5 MT HALEU feedstock completed in FCF: Dec. 2023
 - 5 MT fuel fabrication complete: ~ Dec. 2023
 - If FCF accelerated to 7x24 by June 2022, little no improvement
 - Little to no improvement in schedule to 5 MT fuel
 - Would be needed to maintain 1 MT/yr feedstock rate in later years

Open Issues and Concerns for HALEU Fuel Plan

- **DOE decisions are pending and funding availability has been uncertain**
 - Mitigated by
 - Current focus on facility preparation; not mission-specific
 - Initial engineering and contracting supported by available DOE funds
- **Uncertainty in specific designs and fabrication processes to be supported introduce project and schedule risk**
 - Mitigated by
 - Generic approach to fabrication process
 - INL fuel and process expertise anticipating requirements, to some extent
 - Clear communication to private partner regarding risk and uncertainty
- **Private-partner schedule uncertainty**
 - Mitigated by near-term focus on ASAP provision of fabricated fuel
 - Should meet schedule objectives for all inquirers to date, with one exception



Idaho National Laboratory

COLLABORATIVE COMPUTING CENTER



TRANSIENT REACTOR TEST FACILITY



CYBERCORE INTEGRATION CENTER



Business Sensitive